Payette 30th ~~th~~ Aug 1st 1904

Ordinance No 48

An ordinance relating to the grading and Constructing Cement Side Walks on Boise Street. Ada Avenue. Main Commercial. Broad. and Mill Streets. in the City of Payette.

Be it ordained by the Mayor and Council of the City of Payette.

Section. 1. All side walks hereafter laid on Boise Street. Ada Avenue from Broad to Boise street. Main Street from Broad to Boise street. Commercial Street from Broad to Boise street. Mill Street from Broad to Boise Street. and Broad Street from Main to Mill Street. in the City of Payette shall be Constructed and maintained in the manner and form hereinafter set forth in this Ordinance.

Section. 2. The height of Kerb. shall be Six inches above the established grade of the Street. the same having been established by the City Council.

Section. 3. On Boise Street. on the east side between Grand Avenue and Mill Street. and on the West side. between Ada Avenue and Mill Street. the Side Walks shall be twelve feet wide. measuring from the face of the pilasters on the brick buildings. to the outside of the Kerb. the inside or block line shall be two inches higher than the Kerb.

On Ada Avenue from Broad to Boise Street. On Main Street from Broad to Boise. On Commercial Street from Broad to Boise Street. On Mill Street from Broad to Boise Street. And on the

east side of Broad Street from Main to Mill street. the side Walks shall be eight feet eight inches wide from the pilasters on the buildings to the Outside of the Kerb.

Lines and levels will be supplied by the City Engineer before the Commencement of the Work.

The ground on the outside of the Kerb to be graded with earth to four inches below the top of Kerb.

Specification

Excavation. After the line and grade stakes have been given by the City Engineer. the ground shall be excavated to a depth of five inches below the top of grade Stakes. the surplus earth to be removed to where directed. on adjoining Street.

The place so excavated shall then be filled with Concrete to a depth of four inches. Composed as follows. Seven parts sand and gravel and one part good Portland Cement. to be well mixed dry. before adding the Water. and to be thoroughly tamped in place. the surface to be then Covered with a Coat of Compo'. Composed of three parts clean sharp sand and one part of the best Portland Cement. to be well trowelled evenly over the entire surface of the Concrete in a Workmanlike manner. —

A line of Kerb eight inches Wide to be shewn on the surface of Walk. and the outside face of the Kerb to be plastered in Cement. —

The ends of the side walks upon each block to be returned with a mitre. the return to correspond in width to the sidewalks herein specified.

Section. 4. All Ordinances in Conflict with this Ordinance are hereby repealed.—

Passed and approved this 1st day of September 1904

Attest G. A. D. Dater
Clerk

Approved F. Brighton
Mayor

CITY OF PAYETTE
INCORPORATED
JULY 16, 1891
CANYON COUNTY, IDAHO.